

Alessandra Valloni

PRELIMINARY DESIGN OF THE CERN ERL TEST FACILITY

EIC14 Workshop on Accelerator Science and Technology for Electron-Ion Collider

17–21 March 2014,


Thomas Jefferson National Accelerator Facility

EIC14



Goals of a CERN ERL Test Facility

- Test facility for SCRF cavities and modules
- Test facility for multi-pass multiple cavity ERL
- Injector studies: DC gun or SRF gun
- Study reliability issues, operational issues!
- Vacuum studies related to FCC
- Test facility for controlled SC magnet quench tests
- Possible use for detector development, experiments and injector suggests ~1 GeV as final stage energy
- Could it be foreseen as the injector to LHeC ERL and to FCC?




Goals of a CERN ERL Test Facility

- Test facility for SCRF cavities and modules
- Test facility for multi-pass multiple cavity ERL
- Injector studies: DC gun or SRF gun
- Study reliability issues, operational issues!
- Vacuum studies related to FCC
- Possible use for detector development, experiments and injector suggests ~1 GeV as final stage energy
- Test facility for controlled SC magnet quench tests
- Could it be foreseen as the injector to LHeC ERL and to FCC?

TARGET PARAMETER*	VALUE
Injection Energy [MeV]	5
Final Beam Energy [MeV]	900
Normalized emittance $\gamma\epsilon_{x,y}$ [μm]	50
Beam Current [mA]	10
Bunch Spacing [ns]	25 (50)
Passes	3

*in few stages



Outline

1. STAGES OF BUILDING DESIGN

- LAYOUTS
- BASELINE PARAMETERS

2. ARC OPTICS ARCHITECTURE

3. TEST FACILITY FOR SC MAGNET TESTS




Planning for each stage

STEP 1

SC RF cavities, modules and e⁻ source tests

- Injection at 5 MeV
- 1 turn
- 75 MeV/linac
- Final energy 150 MeV

ARC	ENERGY
ARC 1	80 MeV
ARC 2	155 MeV



*4 SRF 5-cell cavities at 802 MHz


Planning for each stage

STEP 2

Test the machine in Energy Recovery Mode

- Injection at 5 MeV
- 3 turns
- 75 MeV/linac
- Final energy 450 MeV

ARC	ENERGY
ARC 1	80 MeV
ARC 2	155 MeV
ARC 3	230 MeV
ARC 4	305 MeV
ARC 5	380 MeV
ARC 6	455 MeV



Recirculation realized with vertically stacked recirculation passes

Planning for each stage


STEP 3

Additional SC RF modules test

Full energy test in Energy Recovery Mode

- Injection at 5 MeV
- 3 turns
- 150 MeV/linac
- Final energy 900 MeV

ARC	ENERGY
ARC 1	150 MeV
ARC 2	300 MeV
ARC 3	450 MeV
ARC 4	600 MeV
ARC 5	750 MeV
ARC 6	900 MeV



Outline



1. STAGES OF BUILDING DESIGN

- LAYOUTS
- BASELINE PARAMETERS


2. ARC OPTICS ARCHITECTURE FOR STEP 3

3. TEST FACILITY FOR SC MAGNET TESTS


Layout




Linac 1 Multi-Pass Optics




Linac 2 Multi-Pass Optics




Arc 1 optics




Arc 3 optics




Arc 5 optics



Arc 1,3,5 layout




- Synchronous acceleration
Isochronous arcs
- Achromatic arc
- FMC optics



Total Arc length for Arc 1,2,3
34.5112 m
 $94 \times \lambda_{rf}$

For 6 arcs:
84 DIPOLES
114 QUADRUPOLES

Footprint



ARCS

Total length for Arc 1,2,3

34.5112 m

$94 \times \lambda_{rf}$

(last cavity linac1 to first cavity linac 2)

Total length for Arc 2,4

34.2704 m

$101 \times \lambda_{rf}$

(last cavity linac1 to first cavity linac 2)


Total length for Arc 6

34.4574 m

$101.5 \times \lambda_{rf}$

(last cavity linac 1 to first cavity linac 2)

LINAC



ONE CRYOMODULE: 8 RF CAVITIES

PARAMETER	VALUE
Frequency	801.58 MHz
Wavelength	37.4 cm
$L_{cavity} = 5\lambda/2$	93.5 cm
Grad	20.02 MeV/m
ΔE	18.71 MV per cavity

Total length ~ 13 m



CHICANE INJ/EXTR

Length ~ 1.75 m

TOTAL DIMENSIONS
42 m x 13.7 m

Arc optics OPTION 2

SAME OPTICS LAYOUT FOR ALL THE ARCS 900/750/600/450/300/150 MeV



3 DIPOLES
ON TOP OF
EACH OTHER
* Attilio Milanese

Arc dipoles :

8×22.5° bends

Ldip = 100.6 cm

ρ = 256.3 cm

	1GeV	750MeV	600MeV	450MeV	300MeV	150MeV
--	------	--------	--------	--------	--------	--------

B FIELD	1.30 T	0.97 T	0.78 T	0.58 T	0.39 T	0.19 T
---------	--------	--------	--------	--------	--------	--------

Arc quadrupoles

Lquads = 30 cm

Q1	Q2	Q3	Q4
----	----	----	----

Kq[m ⁻²]

-1.01

2.91

2.09

1.19

Incoherent Synchrotron radiation in return arcs


ARC	E [MeV]	ρ [cm]	ΔE [keV]	$\sigma E/E$ [%]
1	150	91.459	0.0280	1.17e-5
2	300	91.459	0.4191	6.42e-5
3	450	230.66	0.8230	8.13e-5
4	600	230.66	2.5726	1.53e-4
5	750	230.66	6.2394	2.73e-4
6	900	230.66	12.881	4.47e-4
7	750	230.66	6.2394	5.89e-6
8	600	230.66	2.5726	7.49e-6
9	450	230.66	0.8230	9.98e-6
10	300	91.459	0.4191	1.49e-6
11	150	91.459	0.0280	2.93e-3

- Beam Energy loss $\Delta E = \int P_\gamma dt = P_\gamma \frac{\pi \rho}{\beta c} \quad \Delta E(GeV) = C_\gamma \frac{E^4}{\rho} \frac{1}{2}$


- Beam Energy Spread $\frac{\sigma_E}{E} = \sqrt{1.4397 * 10^{-27} \frac{\pi \gamma^5}{\rho^2}}$

Next steps


- Complete Step 2 and Step 1 configuration and optics layout






Linac 1 - Step 2



Linac 2 - Step 2



Step 2 optics



Outline

- Test facility for SCRF cavities and modules
- Test facility for multi-pass multiple cavity ERL
- Test facility for controlled SC magnet quench tests
- Injector studies: DC gun or SRF gun
- Study reliability issues, operational issues!
- Vacuum studies related to FCC
- Possible use for detector development, experiments and injector suggests ~1 GeV as final stage energy
- Could it be foreseen as the injector to LHeC ERL and to FCC?

1. STAGES OF BUILDING DESIGN

- LAYOUTS
- BASELINE PARAMETERS

2. ARC OPTICS ARCHITECTURE

3. TEST FACILITY FOR SC MAGNET TESTS

Controlled quench tests of SC magnets

WE ARE INVESTIGATING THE POSSIBILITY OF USING THE TEST FACILITY
FOR SC MAGNET TESTS

Requirements in terms of:


- Beam energy, intensity and pulse length (energy deposition)
- Space for the magnets installation (possible tests of cable samples and full cryo magnets)
- Cryo requirements
- Vacuum requirements
- Powering needs



Controlled quench tests of SC magnets

Study beam induced quenches (quench thresholds, quenchino thresholds) at different time scales for:

- SC cables and cable stacks in an adjustable external magnetic field
- Short sample magnets
- Full length LHC type SC magnets




Quench limits of LHC dipole as expected from QP3 simulations for different pulse durations

Courtesy A. Verweij

Beam parameters to generate a given amount of energy deposition

CALCULATIONS AND FLUKA SIMULATIONS




Beam parameters

Energy, MeV	Emittance, m	Sigma, cm	FWHM, cm
150	1.70E-07	0.092	0.22
300	8.52E-08	0.065	0.15
450	5.68E-08	0.053	0.13
600	4.26E-08	0.046	0.11
750	3.41E-08	0.041	0.10
900	2.84E-08	0.038	0.09
1000	2.55E-08	0.036	0.08


Results are given for half of bulky target because of symmetry

Binning: 1 mm³ bins



Beam parameters to generate a given amount of energy deposition

CALCULATIONS AND FLUKA SIMULATIONS




Beam parameters


Energy, MeV	Emittance, m	Sigma, cm	FWHM, cm
150	1.70E-07	0.092	0.22
300	8.52E-08	0.065	0.15
450	5.68E-08	0.053	0.13
600	4.26E-08	0.046	0.11
750	3.41E-08	0.041	0.10
900	2.84E-08	0.038	0.09
1000	2.55E-08	0.036	0.08

Results are given for half of bulky target because of symmetry


Binning: 1 mm³ bins




Beam parameters to generate a given amount of energy deposition



Depth of max dE/dx





Max energy deposition



Beam parameters to generate a given amount of energy deposition

electrons needed to quench the magnet = Quench threshold
 Maximum value for the energy deposition

MB quench limit @ 3.5 TeV



$$1 \text{ GeV} = 1.602 \times 10^{-7} \text{ mJ}$$

MB quench limit 450 GeV is 140mJ/cm³ in 10ms:

$$\sim 2.2 \times 10^9 \text{ e}^- \text{ @ 1GeV necessary}$$

MB quench limit 7 TeV is 16 mJ/cm³ in 10ms:

$$\sim 2.6 \times 10^8 \text{ e}^- \text{ @ 1GeV necessary}$$

Summary

- The concept of the ERLTF is designed to allow for a staged construction with verifiable and useful stages for an ultimate beam energy in the order of 1 GeV.
- Design complementary to & synergetic with other proposals
- A Design Study of the ERL-TF has started (a sketch of the optics configuration is provided and other options are under investigation) in collaboration with other institutes (as JLAB)
- First analysis of having controlled quench tests of next generation superconducting magnets has been carried out. Beam parameters seem to match the requirements....further investigation is required!
- Completion of Conceptual design study of an ERL-TF at CERN by the end of 2015

Thank you for your attention

Many thanks to A. Bogacz , V. Chetvertkova, D. Wollmann, and the
LHeC Study Group Collaboration

